



ISO 9001:2015
ISO 14001:2015
ISO 22000:2005
ISO 15378:2015
ISO 22716:2007

FDA-HALAL-BSCI-GMP

HCSP CO., LTD

PERFECT MOISTURE CONTROL TECHNIQUE

Head Office : Secco Americas, Biscayne Blvd, PH-N, Miami, FL 33137, USA.

Factory 1: No.518, To Ngoc Van road, Tam Phu ward, Thu Duc District, HCM, Viet Nam

Factory 2: No. 418, Binh Duong Highway, An Thanh, Thuan An, Binh Duong, Vietnam

Tel : (84-8) 38978059

Website: www.secco.vn

TEST REPORT

PRODUCT NAME: Montmorillonite Desiccant 0.5-2 mm

Date	Weight (gr)	Temperature (°C)	Humid (%)	Water absorption (%)
1	6,00	25	90	0,00%
2	6,10	25	90	1,72%
3	6,15	25	90	2,58%
4	6,21	25	90	3,44%
5	6,26	25	90	4,30%
6	6,31	25	90	5,16%
7	6,36	25	90	6,02%
8	6,41	25	90	6,88%
9	6,46	25	90	7,74%
10	6,52	25	90	8,60%
11	6,57	25	90	9,46%
12	6,62	25	90	10,32%
13	6,67	25	90	11,18%
14	6,72	25	90	12,04%
15	6,77	25	90	12,90%
16	6,83	25	90	13,76%
17	6,88	25	90	14,62%
18	6,93	25	90	15,48%
19	6,98	25	90	16,34%
20	7,03	25	90	17,20%
21	7,08	25	90	18,06%
22	7,14	25	90	18,92%
23	7,19	25	90	19,78%
24	7,24	25	90	20,64%
25	7,29	25	90	21,50%



ISO 9001:2015
ISO 14001:2015
ISO 22000:2005
ISO 15378:2015
ISO 22716:2007

FDA-HALAL-BSCI-GMP

HCSP CO., LTD

PERFECT MOISTURE CONTROL TECHNIQUE

Head Office : Secco Americas, Biscayne Blvd, PH-N, Miami, FL 33137, USA.

Factory 1: No.518 , To Ngoc Van road , Tam Phu ward, Thu Duc District, HCM, Viet Nam

Factory 2: No. 418, Binh Duong Highway, An Thanh, Thuan An, Binh Duong, Vietnam

Tel : (84-8) 38978059

Website: www.secco.vn

Summary:

Material No.	Before testing (g)	After testing (g)	Water absorbed (g)	Water absorbed (%)
1	6,00	7,29	1,29	21,50%

QC

Truong Minh Vuong

Director



Mr Tran Huu Hien (Ph.D)